

PIT THERMAL ENERGY STORAGE EXPERIENCES FROM TOFTLUND

Christian Teil Fyhn Chief project manager. Ramboll Energy



AGENDA

- Case Toftlund
 - Key facts
 - Main experiences
 - Update on the performance



TOFTLUND PTES - KEY FACTS

Fact	
Operation start	June 2017
Size	85.000 m3
CAPEX	21 mill. DKK (~247 DKK/m3)
Charging capacity	18 MW
Discharging capacity	8 MW
Heat source	Primarily solar thermal 27.000 m2 and heat from a 3 MW absorption heat pump operated with heat from a gas fired boiler or an electrical boiler. Absorption heat pump cools down the storage in the winter period. Indirectly heat from CHP (7,2 MWheat).
Lid construction	1,5 mm HDPE liner as top liner Insulation – 600 mm Leca (Expanded clay) 2,5 mm HDPE liner as floating cover





TOFTLUND - MAIN EXPERIENCES

- Lid construction still works as intended,
 - Approx. 2/3 of the insulation was flooded in the commissioning phase, due to a extreme rain.
 In the following phase it has shown possible to completely dryout the insulation and the insulation properties is restored without replacement of the insulation material.
 - Minor leakage from the floating cover (2-3 m3/day). Water is reinjected via a central pump system. Leakage level is not critical for the time being but seams slightly increasing.
- Rain water handling system works satisfactorily in accordance to the operator.
 - Some puddles needs to be drained manually, but in general the system works automatically.










TOFTLUND - UPDATE ON THE PERFORMANCE

DATA FROM TOFTLUND (85.000 M3 STORAGE/27.000 M2 SOLAR/CHP/EL BOILER/GAS BOILER)



Total realized heat loss

- 4.377 MWh in 2018 wet insulation rainwater entered the lid construction during the commissioning phase.
- 2.808 MWh in 2019 active drying of the insulation until April/May.
- 2.374 MWh 2020 corresponding to the design.

Calculated heat loss

Approx. 2.650 MWh/year – calculated based on the operating profile for 2019.

The heat loss has the last year stabilized at the current level of around 2.350 MWh, when seen 12 month back. <u>Conclusion: The storage is performing in accordance with the design.</u>



QUESTIONS?

Contact information's

Christian Teil Fyhn
Chief Project Manager
District Energy Production

M +45 5161 1009 chtf@ramboll.com

THANK YOU!

